



Millwood Station Banquet Facility Fire & Rescue Company 21

The building contains a 78' by 58' bingo hall with an office and storage room attached. The 98' x 58' banquet hall can be divided with the moveable partition. The banquet hall facilities include a large entrance foyer with central fireplace, offices, coat room, men's and women's bathrooms and changing rooms, two large storage rooms and two bar service areas. A central core between the banquet hall and bingo hall share a large commercial kitchen and additional bathrooms.

The exterior walls are constructed with split face reinforced concrete masonry units at the bingo hall and split face concrete masonry units applied over light gage steel stud framing at the banquet hall and service area. The roof covering is standing seam metal.



Millwood Station Banquet Facility Fire & Rescue Company 21

Location: Winchester, VA

Architect: Design Concepts,
Winchester, VA

Area: 15,800 ft²

Floor System: Concrete Slab
on Grade

Roof System: Pre-Engineered
Wood Trusses

Lateral System: Reinforced
Concrete Masonry Shear
Walls at the Bingo Hall.
Wood panel sheathing
over light gage wall stud
framing at the banquet
hall and service facilities.

Completion Date: 2004